

Mobile: **69012-99910**
E-mail: ain@awesindia.edu.in
Website: ainguwahati.org

Army Institute of Nursing
Guwahati
C/O 151 Base Hospital
Basistha, Guwahati-781029

205/QF/AIN/DINING/SAMPRITI/07

10 Mar 2025

CALL FOR QUOTATION FOR REPAIR AND RENOVATION OF THE DINING HALL FOR THE SAMPRITI BUILDING IN OLD AIN HOSTEL

1. Army Institute of Nursing, Guwahati intends to carry out repair and renovation of the Dining hall in the 'Sampriti block' in old AIN Hostel. Quotations are invited for repair and renovation as per the scope of work attached as **Appendix**.
2. Site inspection/ visit can be carried out to assess the work on all working days between 11.00 AM and 1.00 PM. Work will be explained on ground by the representative of hostel. The "Sampriti Building" is located in old AIN Hostel inside HQ 51 Sub Area near Panjabari TCP Gate.
3. Quoted rate must be inclusive of GST and applicable charges. Quotation must have proper mailing address, email ID and contact number and supported with GST registration certificate and PAN card of the firm/individual. Quotations not as per the requisition will be rejected.
4. Quotation in sealed envelope title as **"Repair and renovation of Dining hall in Sampriti block in old hostel"** to be dropped in the quotation box kept in the office of AIN, Guwahati, C/O 151 Base Hospital, Basistha Temple Road, Guwahati-781029 by latest on **15 March 2025 before 11.00 hours**.
5. The work will be subjected for inspection to ascertain the conformity of the specification (Scope of work) as laid down in the supply order by following: -
 - (i) Representative of Contractor.
 - (ii) Representative of AIN Guwahati.
6. The contractor is liable to rectify any defect/faults due to unskilled/casual labour.
7. No payment will be made if the instruction/specification given in the quotation or work order is not adhere to or violated. Any defective, damaged or wrong work will be not accepted by the Institute and the same must be replaced/rectified as specified in the quotation or as directed.
8. Payment will be made through the local cheque by this Institute on submission of the bills subject to the completion and acceptance of the work by the Board of officer detailed by the Institute.
9. This quotation is being issued with no financial commitment and the Buyer reserves the right to change or vary any part thereof at any stage. Further the Buyer also reserves the right to withdraw the quotation, should it become necessary at any stage.
10. The District Court, Kamrup (M) shall alone have the jurisdiction to decide any dispute arising out of or in respect of the contract.



Col Jyoti Prasad Saikia
Registrar & HoA
AIN Guwahati

Encls: As above

Appendix

(Refer to call for quotation no. 205/QF/AIN/DINING/SAMPRIITI/07

Dt 10 Mar 2025)

SN	Particulars	Qty
01	Materials and labour for the installation of the veranda (Roof over the pavement of Dining Hall) Specification: H- 12 ft ,W- 10 ft L-24mtr 48 OD MS pipe 400kg , Dura roof 0.45mm-85sqmtr, Post PCC 1ft x 1ft x 2ft – 09pcs Iron truss and post painting.	01 job
02	Materials and labour for veranda floor with PCC (Pavement)Specification: 14 mtr x 3ft x 6”	01 job
03	Materials and labour for Footpath repairing with PCC (a) 96 ft x 4 ft, (b) 32 ft x 6.5 ft	01 job
04	Materials and labour for 02 coats of acrylic distemper for internal surfaces over a coat of wall primer after necessary preparation of surface by cleaning using sand paper	376 sqmtr
05	Materials and labour for 02 coats of weather coat over a coat of wall primer after necessary preparation of surface by cleaning using sand paper	250 sqmtr
06	Materials and labour for the installation of fly proof mesh for Door-05 and windows- 11 Door size: 6 ft x 3ft, Window: 4 x 3 ft	01 job
07	Materials and labour for the repairing of wooden mesh doors with fittings	01 job
08	Materials and labour for the installation of Iron Grill for the 1 x window and 1 x Aluminium window frame with Glass. Window: 4 x 3 ft	01 job
09	Materials and labour for 2 coats of synthetic enamel paint over Metal surface and wooden surface	01 job
10	Materials and labour for the installation of vinyl flooring 1 mm Area: 20 ft x 40 ft. Preparing the surface for the installation of the Vinyl flooring with PCC etc, completed finish	800sqft
11	Supply and fittings for LED 20W tube lights. Extra electrical connections with switch and sockets for LED lights Make: Havells/Anchor/Syska/Finolex	26 nos
12	Materials and labour for installation of an Iron pole for electrical main line redressing.	02 nos
13	Materials and Labour for fixing and restoring the existing concertina coil fence to strengthen the fencing	61 Rm
14	Materials and labour for Angle Iron Grill Gate with fittings. 250 Kg	01 job
15	Materials and Labour for fixing and restoring the existing boundary wall with both side plaster and white washing completed finish. Wall height 6ft	01 job
16	Materials and labour for construction of brick wall 5” with both side plaster, underground 2 ft deep 6ft height’ New 25.60Rm and white washing 170 sqmtr (both side)	01 job
17	Materials and labour for the fitting of curtains rod with bracket and accessories etc	01 job
18	Minor Misc cement repair work/minor plumbing repair work/minor Electric repair work/minor carpenter repair work/building joints/any sort of refixing work involving 1 skilled and 1 helper in any category	01 job